



VIRGINIA POLYTECHNIC INSTITUTE AND STATE UNIVERSITY
PROCUREMENT DEPARTMENT

ADDENDUM NO. 2

DATE: April 7, 2026
TO: All Offerors
FROM: Kim Widrig, Contracting Officer
TOTAL PAGE(S): 2 pages (not including attachments)
SOLICITATION TITLE: McBryde Hall Toilets Floors 1-3
SOLICITATION NUMBER: 049302620

I. CLARIFICATIONS AND ADDITIONAL INFORMATION

1. The due date has been changed to April 17 at 2:00 PM. The bid opening will take place at 2:00 PM on April 20 at the same Zoom link on the Notice of Invitation for Bids form (page 5 of the Project Manual).

II. REQUESTS FOR INFORMATION

1. On page A-211 the wall tile is indicated behind toilet fixture areas and lavatory areas, with a very clear indication of the area the wall tile is to cover. However, on page A-201 there is no indication that there is to be any wall tile in these restrooms. Are we interpreting the drawings correctly?

Virginia Tech Response: *Please see the attached sketch for walls to receive tile in the first floor restrooms.*

2. The wall tile specified on the drawings is no longer available, it was discontinued in December.

Virginia Tech Response: *The tile that was discontinued will be replaced with what is used on second and third floor tile called out in the finish list.*

3. There are discrepancies between Sheets A-201 and A-211 regarding the selected floor materials and wall finishes in Rooms B04, B15, C13, and C17. Please clarify the correct floor and wall tile finishes for these rooms, as well as for Rooms A28, A27, A09, and A11 (these rooms are not shown on Sheet A-211—see item below).

Virginia Tech Response: *Provide what is called for in the A-211 Finish list for the second and third floors.*

4. Additionally, Sheet A-211 indicates wall tile finishes (via dashed line in the finish legend, denoting “new wall tile”) for Rooms B04, B15, C13, and C17; however, these indications are not shown for Rooms A28, A27, A09, and A11.

Virginia Tech Response: *Please see the attached sketch for walls to receive tile in the first floor restrooms.*

5. Please verify whether the intent is to use Mapei Aquadefense with reinforced fabric as a crack isolation system in lieu of a Schluter waterproofing system, and confirm whether a mud bed is to be included, as it is not currently indicated. If a mud bed is required, please note that a smaller floor tile will be needed, such as PT-1 (2" x 2") as shown in the drawings, rather than the 24" x 24" terrazzo tile, which appears to conflict with Sheet A-211.

Virginia Tech Response: Provide crack isolation as specified. Virginia Tech requires 24"x24" terrazzo tile. Prep floors to receive terrazzo tile.